FLOOR LEVEL	DOOR NO.	TYPE	LOCATION (ROOM NO.)	SIZE		DOOR		FRAME		HINGE	MANUAL FLUSH BOLT	LEVER TRIM	STOREROOM LEVER LOCK	PRIVACY LEVER LOCK	DEADBOLT (DOUBLE CYLINDER)	EXIT DEVICE	MORTISE CYL. FOR EXIT DEVICE	DOOR CLOSER	PULL PLATE	PUSH PLATE	KICK PLATE	DOOR STOP	DOOR SILENCER	MALE/FEMALE GRAPHIC SYMBOL	REMARKS
				WIDTH	HEIGHT	MATERIAL	FINISH	MATERIAL	FINISH																
FIRST FLOOR																									
	D.201A	2	Corridor (201)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.202	2	Bedroom #4 (202)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.202A	1	Washroom #8 (202A)	800	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.204	2	Master Bedroom (204)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.204A	2	Closet (204A)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.204B	2	Washroom (204B)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.206	2	Family Room (204B)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.207	2	Prayer Room (207)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.208	2	Bedroom #2 (208)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.208A	1	Washroom #6 (208A)	800	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●	●							●				●	●		
	D.209	2	Laundry (209)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.210	2	Bedroom #3 (210)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.210A	1	Washroom #7 (210A)	800	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.210B	8	Balcony (210B)	1200	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.211	2	Bedroom #1 (211)	900	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		
	D.211A	1	Washroom #5 (211A)	800	2100	Solid Core flush plywood	Laminated / hardwood edge	Aluminium	Annodized	●								●				●	●		

FOR CONSTRUCTION

NOTES:

JASPAL BHOGAL Associates
Architects and Design Consultants

8A Saddle Road, Maraval,
Trinidad, West Indies TEL:
(868) 628-1852
FAX: (868) 628-7239

RENOVATIONS
INDIA HOUSE
21-23 TRINIDAD CRESENT, FEDERATION PARK, P.O.S.

DOOR SCHEDULE II

Drawn by: -	Client: The Indian High Commission 6A Victoria Avenue, POS	
Scale: AS SHOWN		
Date: APRIL-2013	Sheet Number:	Issue Date: 10-Aug-15
Status: -	A-604	Revision: -

This document, and the ideas and design incorporated herein, as an instrument of professional service, is the property of JASPAL BHOGAL Associates and is not to be used in whole or in part, for any other project without prior written authorization.