1 DOOR
A-501 1:50

2 DOOR
A-501 1:50

3 DOOR
A-501 1:50

4 DOOR
A-501 1:50

5 DOOR
A-501 1:50

6 DOOR
A-501 1:50

7 DOOR
A-501 1:50

8 DOOR
A-501 1:50

DOOR SCHEDULE									
DOOR	DOOR		FRAME		SIZES				WINDOW LOCATIONS
	MATERIAL	FINISH	MATERIAL	FINISH	A	B	C	D	
1	Wood		Aluminum		800	2100	–	–	Main entrance, Powder room, Washroom #1–#8
2	Wood		Aluminum		900	2100	–	–	Living room, Dining room, Study, Kitchen, Pantry, Carport, Caretaker Bedroom, Male washroom #4, Female Washroom#3, Male changing, Female changing, Servery, Bedroom #1–#4, Laundry, Corridor, Prayer room, Family room, Master bedroom, Closet, Wash room and Corridor
3	Glass		Aluminum		1600	2100	–	–	Living room
4	Wood		Aluminum		1696	2100	–	–	Main Entrance
5	Wood		Aluminum		2000	2100	–	–	Storage
6	Wood		Aluminum		1700	2100	–	–	Corrioor
7	Wood		Aluminum		1600	2100	–	–	Storage
8	Wood		Aluminum		1200	2100	–	–	Balcony

FOR CONSTRUCTION

NOTES:

-External doors to match height of existing

REVISIONS:

Date:	Details:
January 2017	

JASPAL BHOGAL Associates
Architects and Design Consultants
8A Saddle Road, Maraval,
Trinidad, West Indies TEL:
(868) 628-1852
FAX: (868) 628-7239

RENOVATIONS
INDIA HOUSE
21-23 TRINIDAD CRESENT, FEDERATION PARK, P.O.S.

DOOR SCHEDULE

Drawn by: N.R.	Client: The Indian High Commission 6A Victoria Avenue, P.O.S.	
Scale: AS SHOWN		
Date: DEC-2017	Sheet Number: A-501	Issue Date: 13-Dec-17
Status: - -		Revision: -

This document, and the ideas and design incorporated herein, as an instrument of professional service, is the property of JASPAL BHOGAL Associates and is not to be used in whole or in part, for any other project without prior written authorization.