R.C. GROUND BEAM ALONG GRIDLINE 1/A-E REINF'T. DETAILS
R.C. GROUND BEAM ALONG GRIDLINE 3/A-E REINF'T. SIMILAR
SCALE ~ 1:20

SECTION 1
SCALE ~ 1:15

R.C. GROUND BEAM ALONG GRIDLINES 2/B-E REINF'T. DETAILS
SCALE ~ 1:20

SECTION 2
SCALE ~ 1:15

R.C. GROUND BEAM ALONG GRIDLINES 4/A-F REINF'T. DETAILS
SCALE ~ 1:20

SECTION 3
SCALE ~ 1:15

150mm thk. R.C. GROUND FLOOR SLAB SECTION
SCALE ~ 1:15

NOTES

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ARCHITECT'S AND OTHER RELEVANT DRAWINGS.
2. READ FIGURED DIMENSIONS ONLY, DO NOT SCALE.
3. CONCRETE STRENGTH TO BE 25N/mm² CYLINDER STRENGTH AT 28 days.
4. COVER TO MAIN REBARS ARE AS FOLLOWS:

   BEAMS:

   COVER TO SIDE & BOTTOM REINF. : 40mm

   COVER TO TOP REINF. : 25mm
5. BAR LAP LENGTH TO BE 50 x BAR DIAMETER.

FOR INFORMATION
10th December, 2019

DATE	No	REVISION

KS&P LTD
Consulting Civil & Structural Engineers
1st Floor, #8 Roberts Street, Woodbrook
Port of Spain, Trinidad, W.I.
Phone: 868-622-0130/1 Fax: 868-628-5484
Email: info@kspltd.com Website: www.kspltd.com

ARCHITECT:
JASPAL BHOGAL Associates
Architects and Design Consultants
8A Saddle Road, Maraval,
Trinidad, West Indies TEL:
(868) 628-1852
FAX: (868) 628-7239

PROJECT:
RENOVATIONS
INDIA HOUSE
21 - 23 TRINIDAD CRESCENT,
FEDERATION PARK, P.O.S.

TITLE: **R.C. GROUND FLOOR BEAMS REINF'T DETAILS (SHEET #1)**

DATE:	30th. April, 2018
SCALE:	AS SHOWN
DRAWN:	C.C.
CHECKED:	K.S.
DRAWING No:	**18/0012/S-08**
REV. No.	**0**