SECTION 1-1
SCALE ~ 1:15

TYP. 900sq. x 300dp. R.C. PAD FOOTING MK'D 'F1' REINF'T. DETAILS
SCALE ~ 1:15

TYP. 150mm thk. R.C. BLOCKWALL ON 450wd x 300dp. R.C. STRIP FOOTING REINF'T. DETAILS
SCALE ~ 1:15

R.C. COLUMN 'C1' REINF'T. DETAILS
SCALE ~ 1:15

SECTION 1-1
SCALE ~ 1:10

'C2' COLUMN
SCALE ~ 1:10

'C3' COLUMN
SCALE ~ 1:10

NOTES

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ARCHITECT'S AND OTHER RELEVANT DRAWINGS.
2. READ FIGURED DIMENSIONS ONLY, DO NOT SCALE.
3. CONCRETE STRENGTH TO BE 25N/mm² CYLINDER STRENGTH AT 28 days.
4. COVER TO MAIN REBARS ARE AS FOLLOWS:

   FOUNDATION:

   COVER TO TOP REINF. : 75mm

   COVER TO BOTTOM REINF. : 75mm

   COLUMNS:

   COVER TO REINF. : 50mm
5. BAR LAP LENGTH TO BE 52 x BAR DIAMETER.

FOR INFORMATION
10th December, 2019

DATE	No	REVISION

KS&P LTD
Consulting Civil & Structural Engineers
1st Floor, #8 Roberts Street, Woodbrook
Port of Spain, Trinidad, W.I.
Phone: 868-622-0130/1 Fax: 868-628-5484
Email: info@kspltd.com Website: www.kspltd.com

ARCHITECT:
JASPAL BHOGAL Associates
Architects and Design Consultants
8A Saddle Road, Maraval, Trinidad, West Indies TEL: (868) 628-1852 FAX: (868) 628-7239

PROJECT:
RENOVATIONS
INDIA HOUSE
21 - 23 TRINIDAD CRESCENT,
FEDERATION PARK, P.O.S.

TITLE: **R.C. PAD, STRIP FOOTING & COLUMN REINF'T DETAILS (SHEET #1)**

DATE:	30th. April, 2018
SCALE:	AS SHOWN
DRAWN:	C.C.
CHECKED:	K.S.
DRAWING No:	18/0012/S-07
REV. No.	0