101 WINDOW
A-500 1:50

102 WINDOW
A-500 1:50

103 WINDOW
A-500 1:50

104 WINDOW
A-500 1:50

105 WINDOW
A-500 1:50

106 WINDOW
A-500 1:50

107 WINDOW
A-500 1:50

WINDOW SCHEDULE

WINDOW NUMBER	WINDOW		FRAME		SIZES				DOOR LOCATIONS
	MATERIAL	FINISH	MATERIAL	FINISH	A	B	C	D	
101	Aluminum & Glass		Aluminum		1200	600	1800	–	Washroom #9, Master bedroom closet, Washroom #7
102	Aluminum & Glass		Aluminum		1200	950	1450	–	Kitchen, Caretakers bedroom, Server room,Prayer room, Bedroom #1, Kitchenette and Master bedroom
103	Aluminum & Glass		Aluminum		900	600	1800	–	Powder room, Washroom #1, Male washroom #4, Female bathroom #3, Washroom #8, Corridor, Washroom #6
104	Aluminum & Glass		Aluminum		1200	1850	550	–	Bedroom #4
105	Aluminum & Glass		Aluminum		1763	950	1450	–	Master bedroom
106	Aluminum & Glass		Aluminum		1200	1850	550	–	Dining room
107	Aluminum & Glass		Aluminum		1763	1250	1150	–	Bedroom #3, Bedroom #1 and Bedroom #2

FOR CONSTRUCTION

NOTES:

REVISIONS:

Date:	Details:
January 2017	

JASPAL BHOGAL Associates
Architects and Design Consultants
8A Saddle Road, Maraval,
Trinidad, West Indies TEL:
(868) 628-1852
FAX: (868) 628-7239

RENOVATIONS
INDIA HOUSE
21-23 TRINIDAD CRESENT, FEDERATION PARK, P.O.S.

WINDOW SCHEDULE

Drawn by: N.R.	Client: The Indian High Commission 6A Victoria Avenue, P.O.S.	
Scale: AS SHOWN		
Date: DEC-2017	Sheet Number: A-500	Issue Date: 13-Dec-17
Status: - -		Revision: -

This document, and the ideas and design incorporated herein, as an instrument of professional service, is the property of JASPAL BHOGAL Associates and is not to be used in whole or in part, for any other project without prior written authorization.