FLOOR LEVEL	DOOR NO.	TYPE	LOCATION (ROOM NO.)	SIZE		DOOR		FRAME		HINGE	MANUAL FLUSH BOLT	LEVER TRIM	STOREROOM LEVER LOCK	PRIVACY LEVER LOCK	DEADBOLT (DOUBLE CYLINDER)	EXIT DEVICE	MORTISE CYL. FOR EXIT DEVICE	DOOR CLOSER	PULL PLATE	PUSH PLATE	KICK PLATE	DOOR STOP	DOOR SILENCER	MALE/FEMALE GRAPHIC SYMBOL	REMARKS
				WIDTH	HEIGHT	MATERIAL	FINISH	MATERIAL	FINISH																
GROUND FLOOR																									
	D.102	4	Entrance (101)	1696	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●					●			●				●	●		
	D.102A	1	Powder Room (102A)	800	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●	●		
	D.102	2	Lobby Area (102)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●	●		
	D-103	3	Living Room (103)	1600	2550	Aluminium / Glass	Annodized	Aluminium	Annodized	●								●			●	●			TO BE REFURBISHED & REUSED
	D.103A	2	Living Room (103)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●			●	●			
	D.105	2	Study (105)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●			●	●	●		
	D.106	2	Dining Room (106)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●			●	●	●		
	D.108	2	Severy (108)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●			●	●			
	D.109	2	Kitchen (109)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●			●	●			
	D.110	2	Pantry (110)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●			
	D.111	7	Storage (111)	1600	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●			●					●				●			
	D.112	2	Male Change Room (112)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●				●				●				●		●	
	D.112A	2	Female Change Room (112A)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●				●				●				●		●	
	D.113	6	Corriodor (113)	1700	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●			
	D.114	2	Garage (114)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●			
	D.115	7	Storage (115)	2000	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●			●					●				●	●		
	D.116	1	Washroom #2 (116)	800	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●	●		
	D.117	2	Caretakers Bedroom (117)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●								●				●	●		
	D.118	2	Female Washroom (118)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●				●				●				●	●	●	
	D.119	2	Male Washroom (119)	900	2100	Solid Core flush plyw ood	Annodized	Aluminium	Annodized	●				●				●				●	●	●	

FOR CONSTRUCTION

NOTES:

JASPAL BHOGAL Associates
Architects and Design Consultants

8A Saddle Road, Maraval,
Trinidad, West Indies TEL:
(868) 628-1852
FAX: (868) 628-7239

RENOVATIONS
INDIA HOUSE
21-23 TRINIDAD CRESENT, FEDERATION PARK, P.O.S.

DOOR SCHEDULE II

Drawn by: -	Client: The Indian High Commission, POS 6A Victoria Avenue, POS	
Scale: AS SHOWN		
Date: APRIL-2013	Sheet Number: A-603	Issue Date: 10-Aug-15
Status: -		Revision: -

This document, and the ideas and design incorporated herein, as an instrument of professional service, is the property of JASPAL BHOGAL Associates and is not to be used in whole or in part, for any other project without prior written authorization.